INSTALLATION AND OPERATION MANUAL

Q.PEAK DUO-G9.X solar module series






TABLE OF CONTENTS

| 1 | INTI | RODUCTION | 3 | |
|---|----------------------------|--------------------------------|----|--|
| 2 | PLANNING | | | |
| | 2.1 | TECHNICAL SPECIFICATIONS | 5 | |
| | 2.2 | REQUIREMENTS | 6 | |
| | 2.3 | MOUNTING OPTIONS | 7 | |
| | 2.4 | ELECTRICAL LAYOUT | 10 | |
| 3 | INS | 11 | | |
| | 3.1 | SAFETY AND TRANSPORT | 11 | |
| | 3.2 | PREPARATION OF INSTALLATION | 13 | |
| | 3.3 | MODULE INSTALLATION | 14 | |
| 4 | ELE | 15 | | |
| | 4.1 | SAFETY | 15 | |
| | 4.2 | ELECTRICAL INSTALLATION SAFETY | 16 | |
| | 4.3 | CONNECTION OF MODULES | 17 | |
| | 4.4 | AFTER INSTALLATION | 18 | |
| 5 | GROUNDING | | 19 | |
| 6 | FAULTS AND DEFECTS | | 19 | |
| 7 | DISPOSAL | | | |
| 8 | MAINTENANCE AND CLEANING 2 | | | |

1 INTRODUCTION

With solar modules from Hanwha Q CELLS GmbH (hereafter referred to as "Q CELLS") you can directly transform the sun's limitless energy into environmentally-friendly solar electricity. In order to ensure the maximum performance of your Q CELLS solar modules, please read the following instructions carefully and observe all guidelines. Non-compliance may result in damage and/or physical injury.

This installation and operation manual (hereafter also referred to as the "Manual") provides instructions for the safe installation and operation of crystalline solar modules.

- Please read these instructions carefully before proceeding with your installation.
- Please retain these instructions for the life of the solar modules.
- Please ensure that this Manual is available to the operator at all times.
- This Manual should be given to all subsequent owners or users of the solar modules.
- All supplements received from the manufacturer should be included.
- Please observe all other applicable documents.
- If your questions are not satisfactorily answered in the manual, please contact your system supplier.

Additional information can be found on our website at www.q-cells. com.

Intended Use

This manual is valid for Africa, Asia, Europe, Latin America, South America. These instructions contain information regarding the safe handling and use of quality crystalline solar modules from Q CELLS and their installation, mounting, wiring, maintenance and disposal.

Symbols and Labels

The following symbols and labels are used throughout the Manual for ease of use.

| ę | SYMBOL | DESCRIPTION |
|---|----------|---|
| | → | Procedure with one or more steps. |
| | • | Lists of items. |
| | • | Ensure that when carrying out a procedure, you check the results of said procedure. |
| (| 0 | Prohibited. |

DOCUMENT REVISION 01

This Manual is valid for Africa, Asia, Europe, Latin America and South America as of September 1st 2020 for Q.PEAK DUO-G9, Q.PEAK DUO-G9+, Q.PEAK DUO BLK-G9 and Q.PEAK DUO BLK-G9+ solar modules, and replaces all earlier versions.

This manual is subject to change. The data sheets and customer information valid at the point in time when the relevant module was manufactured apply to the installation, mounting, and maintenance procedures for the respective solar modules, as far as no updated document is provided.



Beware of possible danger or damage. Categories:

- Danger: Risk of fatal injury
- Attention: Risk of serious injury or damage to property
- Note: Risk of damage to product

Safety Regulations

In particular the installer as well as the operator of a module is responsible for compliance with all applicable statutory requirements and regulations.

- Unless otherwise specified by any laws or regulations, the following stipulations must be upheld at all times during the installation, operation, and maintenance of the solar modules:
 - This manual.
 - Other applicable stipulations (such as country-specific regulations for pressure equipment, operational safety, hazardous goods, and environmental protection).
 - Regulations and requirements specific to the system.
 - Any applicable laws and requirements, in particular international, country specific, regional laws and stipulations governing the planning, installation, and operation of solar power systems and work on roofs.
 - Any valid international, national and regional regulations governing work with direct current, especially those applicable to the installation of electrical devices and systems, and regulations issued by the respective energy provider governing the parallel operation of solar power systems.
 - Any international, country specific and regional accident-prevention regulations.
 - Other applicable stipulations provided by the relevant national institutions regarding safety in the installation and operation of electrical items.

Qualified and Skilled Personnel

Both, the installer and operator are responsible for ensuring that the installation (including connection to the grid), maintenance and dismantling are carried out by trained and qualified specialists with approved training certificates (issued by a state or federal organization) for the respective specialist trade. Electrical work may only be performed by an officially certified tradesperson in accordance with the stipulations applicable in the relevant country with regard to standard and regulations (in Germany e.g. DIN standards, VDE regulations) and the stipulations of the local grid operator and/or energy provider.

INTRODUCTION 1

Validity

These instructions are only valid for crystalline solar modules from the company Q CELLS as specified at chapter "2.1 Technical Specifications". Q CELLS assumes no liability for damage resulting from failure to observe these instructions.

- Please observe the wiring and dimensioning of the system.
- → The installer of the system is responsible for compliance with all necessary safety regulations during set-up and installation. Q CELLS assumes no liability on the basis of these instructions. Q CELLS is only liable in the context of contractual agreements or in the context of accepted guarantees. Q CELLS accepts no other responsibility for the functionality and safety of the modules.
- > Please observe the instructions for any other system components that may be part of the complete solar power system. It may be necessary to carry out a structural analysis for the entire project.

Additional information for the Operator

- > Please keep this manual for the entire life of the solar power system.
- Please contact your system supplier for information concerning the formal requirements for solar power systems.
- > Please be sure to contact the relevant local authorities and energy providers regarding regulations and permit requirements prior to installation of the solar power system. Your financial success depends on the fulfillment of these requirements.

Other applicable documents

In addition to this Manual following technical information are relevant:

DOCUMENT TYPE

Product data sheet

Packaging and transport information

PLANNING 2 2.1 TECHNICAL SPECIFICATIONS

For additional information see the relevant datasheet of the module provided at www.q-cells.com.

| PRODUCT LINE | Q.PEAK DUO-G9 Q.PEAK DUO-G9+ | Q.PEAK DUO BLK-G9 Q.PEAK DUO BLK-G9+ | | |
|---|--|---|--|--|
| Туре | Q.ANTUM DUO Z | Q.ANTUM DUO Z | | |
| Length | 1673 mm | 1673 mm | | |
| Width | 1030 mm | 1030 mm | | |
| Frame height | 32 mm | 32mm | | |
| Area | 1.72 m ² | 1.72 m ² | | |
| Weight | 17.5 kg | 17.5 kg | | |
| Max. system voltage V_{sys} | 1000V | 1000V | | |
| Max. reverse current | 20 A | 20 A | | |
| Permissible temperature range | -40 °C to +85 °C (-40 °F to +185 °F) | | | |
| Junction box protection class | IP67 with bypass diode | | | |
| Connector protection class | IP68 | IP68 | | |
| Fire rating based on ANSI / UL 61730 | C/Type 2 | C/Type 2 | | |
| Max. test load Push/Pull ¹ | 6,000 Pa / 4,000 Pa | 6,000 Pa / 4,000 Pa | | |
| Max. design load Push/Pull ¹ | 4,000 Pa/2,660 Pa | 4,000 Pa/2,660 Pa | | |
| Certificates | CE-compliant; IEC 61215:2016; IEC 61730:2016; PV module classification: Class II; UL 61730 | | | |

¹ Test and design load in accordance with IEC 61215:2016, depending on mounting options (see section "2.3 Mounting Options")





Fig. 1: External dimensions and components for Q.PEAK DUO-G9, Q.PEAK DUO-G9+, Q.PEAK DUO BLK-G9 and Q.PEAK DUO BLK-G9+



PLANNING 2.2 REQUIREMENTS

PLANNING 2.3 MOUNTING OPTIONS

Installation Site

Please note the following guidelines that apply to the installation site:

- Solar modules are not explosion-proof and are not suitable for use in explosive environments.
- > Do not operate solar modules near highly flammable gas and vapors (e.g. gas tanks, gas stations).
- Do not install modules in enclosed space.
- Do not install modules in locations where they may be submerged in water (e.g. floodplains).
- > Do not use modules as a substitute for the normal roofing (e.g. modules are not watertight).
- > Do not install modules in close proximity to air conditioning systems
- → Do not install modules above 4000 m (13120 ft) altitude above sea level.
- > Contact with saline water (e.g. spray water from the sea) and salt aggregation on the modules must be avoided.
- Do not bring any chemical substance (e.g. oil, solvent etc.) into contact with any part of the panel. Only substances, which are released by Q CELLS, are allowed to be used during installation, operation and maintenance.
- → Any installation of modules on surfaces of water is prohibited. This includes installations on floating as well as pile-based platforms. Q CELLS may extend the coverage of its warranty to such installations, based on a case by case assessment of the system design and location. A prior written consent by the warrantor is required in any case.
- The solar modules are designed for the following applications:
- Operating temperatures from -40 °C to +85 °C (-40°F to +185°F).
- Pull loads up to max. 4,000 Pa and push loads up to max. 6,000 Pa (see chapter "Mounting Options").
- Installation using a mounting structure for solar modules.

Prevention of Shadowing Effects

Optimal solar irradiation leads to maximum energy output:

- → For this reason, install the modules so that they face the sun.
- Avoid shadowing (due to objects such as buildings, chimneys) or trees).
- > Avoid partial shading (for example through overhead lines, dirt, snow).

Mounting Structure Requirements

The Modules shall be installed and operated on mounting structures that comply with any applicable laws and stipulations as well as with the following:

- · Conform to the necessary structural requirements.
- Compliant with local snow and wind loads.
- Properly fastened to the ground, the roof, or the façade.

- Forces acting on the module are relayed to the mounting substructure.
- Ensures sufficient rear ventilation of the module.
- Avoid the usage of different metals to prevent contact corrosion.
- Allows for stress-free expansion and contraction due to temperature fluctuations.
- Ensure that no additional forces are applied through the mounting system into the module except for the wind and snow loads. Additional forces and moments of torgue at the mounting positions caused by torsions, displacements or vibrations in the mounting system are not allowed.
- → Ensure that the clamps and the mounting frame are compatible.

Clamp System Recommendations

Use customary clamps that satisfy the following requirements:

- Clamp width: ≥40 mm.
- Clamp height compliant with a 32 mm frame height.
- Clamp depth: 7-12 mm. (applicable for all CL clamping mounting options at section "2.3 Mounting Options")
- Clamps are not in contact with the front glass.
- Clamps do not deform the frame.
- Clamps that satisfy the structural requirements based on the conditions of the installation site according to the applicable regulations and technical standards.
- Long-term stable clamps that securely affix the module to the mounting frame.


Module Orientation Requirements

39

- Vertical or horizontal installation is permitted.
- Ensure that rain and melting snow can run off freely. No water accumulation.
- Ensure that the drainage holes in the frame are not covered. No sealing.



Fig. 2: Installation options for crystalline Q CELLS modules. All dimensions are given in mm. Also observe the maximum test loads and clamping range as specified on the following page. The illustrated installation options apply for both horizontal and vertical module orientation.



PLANNING 2 2.3 MOUNTING OPTIONS

Specifications

| opecifications | | | | | |
|---|--------------------|---|-------------------------------|---------------------------------|------------------|
| MODULE TYPE | MOUNTING OPTION | POSITION OF CLAMPS* [MM] | TEST LOAD PUSH/PULL** [PA] | DESIGN LOAD PUSH/PULL** [PA] | SAFETY FACTOR |
| Q.PEAK DUO-G9 Q.PEAK DUO-G9+ | CL1a | 150 - 450 | 5400/4000 | 3600/2660 | |
| Q.PEAK DUO BLK-G9 Q.PEAK DUO BLK-G9+ | FB1 | 346.5 | | | |
| | FB2 | 346.5 | 3300/4000 | 2200/2660 | |
| | IP1 | - | 3300/3300 | 2200/2200 | |
| | CL1a | 20 - 550 | 2400/2400 | 1600/1600 | 1.5 |
| | CL1b | 20 - 550 | | | |
| | CL3 | 250 - 450 | 3300/4000 | 2200/2660 | |
| | CL5 | short side: 100 - 250 long side: 300 - 450 | 3800/3800 | 2530/2530 | |
| | CL6b | short side: 100 - 250 middle: 640 - 1030**** | 6000/4000 | 4000/2660 | |

The below mounting options are only possible under certain conditions.

| MODULE TYPE | MOUNTING OPTION | POSITION OF CLAMPS* [MM] | TEST LOAD PUSH/PULL*** [PA] | DESIGN LOAD PUSH/PULL*** [PA] | SAFETY FACTOR |
|---|----------------------|-----------------------------|-----------------------------------|-------------------------------------|------------------|
| Q.PEAK DUO-G9 Q.PEAK DUO-G9+ | CL2a (with rails) | 20 - 300 | 2400/2000 | 1600/1330 | 1.5 |
| Q.PEAK DUO BLK-G9 Q.PEAK DUO BLK-G9+ | CL2b (without rails) | 20 - 300 | 2000/2000 | 1330/1330 | |
| | IP2 | - | 2000/2000 | 1330/1330 | |

* Distance between outer edge of module and middle of the clamp; consider further details below.

** Loads according to IEC 61215-2:2016 and UL 61730.

*** Test procedure according to IEC 61215-2:2016 and UL 61730. Loads for these mounting options do not fulfill the requirements of the standards.

**** Rails must not be under the junction box.

2 PLANNING 2.3 MOUNTING OPTIONS

ATTENTION

- the determination of location-specific load requirements.
- CL1a at high loads (5400 / 4000 Pa): The clamp position is variable in the given range but the distance between the clamps along the long side of the module (span) must not be larger than 1070 mm.
- → CL1b: Using of short mounting rails are permissible, if they overlap under the module not more than 210 mm. Minimum height of the short mounting rails should be ≥35 mm (clearance between frame bottom edge and roof top).
- Ensure, that the subconstruction does not touch the junction box (even under load). Ensure that the clamps or insertion profiles etc. do not touch the glass (even under load).
- Ensure, that the connection cables of the junction box do not run between laminate and mounting rails.
- → A minimum support depth of 15 mm is required on the back side of the module for IP1, IP2, CL2b, CL3 and CL6b. The minimum required support depth on the module backside for CL5 is 10 mm on long frame side and 15 mm on short frame side. For IP1 and IP2 the minimum support depth on the front side of the module should be 10 mm.
- → CL1a, CL2a and CL3: Ensure that module frame is fixed directly on the rail of the substructure (no spacer allowed between the module and substructure).
- or avoided by technical measures.
- and washers should have the same material properties.

→ The loads in the table are related to the mechanical stability of the solar modules. The mechanical stability of the mounting system including clamps has to be evaluated by the system supplier. The Q CELLS listed test load values were determined with the following clamp parameters: clamp width = 40 mm and clamp depth = 10 mm. The system installer is responsible for

Module bends under load. Therefore, sharp objects (e.g. screws) must not be mounted near the module backside. Unbalanced snow loads (e.g. snow overhangs, snowdrifts) which result in locally significantly increased loads must be removed

→ Use M8 corrosion-proof screws and washers (diameter ≥15.8 mm or ≥0.62 in) for FB1 and FB2 mounting. Mounting screws

PLANNING 2.4 ELECTRICAL LAYOUT

INSTALLATION 3 **3.1 SAFETY AND TRANSPORT**

Module Selection

For detailed key electrical data, please refer to the actual data sheet referring to the relevant Module (available at www.g-cells.com).

> For maximum energy yields, mismatches of specified electric current (I_{MPP}) of more than 5% should be avoided for all modules connected in series.

Safety Factor

During normal operation, a module may generate a greater current and / or higher voltage than that determined under standardized test conditions. Please use a safety factor of 1.25 for the following:

- Calculating the voltage measurement values (V_{oc}) of components
- Calculating the current measurement values (I_{sc}) of conductors
- · Sizing of control systems connected to the outlets of the solar modules
- Please follow the valid national guidelines for the installation of electrical systems.

Series Connection

Connection of modules in series is only permitted up to the maximum system voltage as listed in the applicable data sheet of all the relevant modules to be installed.

- > Take into account all possible operating situations and all relevant technical norms and regulations when designing the system. It has to be ensured that the maximum system voltage, including all necessary safety margins, is not exceeded.
- > Take the voltage limit of the inverter into account when determining the maximum number of modules in the string.

Parallel Connection

Modules may be damaged by the occurrence of reverse currents (caused by module defects, ground leaks, or defective insulation).

Ensure that the maximum reverse current load capacity indicated in the data sheet is met.

In order to limit reverse currents that may occur, we recommend using the following safety options:

1) Layout with a limited number of parallel connected strings:

Without undertaking further current blocking measures, a maximum of two module strings may be operated in parallel on a single inverter or MPP tracker.

2) Layout with string fuses:

Use overcurrent devices (e.g. fuses) according to the relevant standards in each string. Use gPV-fuses according to IEC 60269-6. Observe the maximum permitted number of strings as indicated in the specifications provided by the respective string fuse manufacturer and the technical guidelines.

NOTE!


When installing different product versions, the lowest minimum permitted reverse current load capacity applies.


Inverters

Inverters with or without transformers may be used.



- ′!`
 - Leave modules in their original packaging until installation.
 - Store the modules securely in cool and dry rooms. The packaging is not weatherproof.







3 INSTALLATION3.1 SAFETY AND TRANSPORT


3 INSTALLATION3.2 PREPARATION OF INSTALLATION







3 INSTALLATION **3.3 MODULE INSTALLATION**










Max. torsion 10 mm/m.



4 ELECTRICAL CONNECTION 4.1 SAFETY

DANGER!


Risk of fatal injury due to electric shock!


When disconnecting an electric circuit carrying direct current, electric arcs can occur that may result in life-threatening injuries.

- Do NOT unplug the cable when under load.
- → Do NOT connect any exposed cable ends.
- Electrical work may only be performed by qualified and skilled personnel (see page 3).

A solar module generates electrical current and voltage even at a low intensity of illumination. Sparks and electric arcs may result from the separation of a closed circuit. These can result in life-threatening injuries. The danger increases when several modules are connected in series.


- > Please be aware of that the entire open circuit voltage is active even at low levels of solar irradiation.
- Please follow the valid national regulations and safety guidelines for the installation of electrical devices and systems.
- → Please make sure to take all necessary safety precautions. With module or phase voltages of more than 120 V, the safety extra-low voltage range is exceeded.
- Carry out work on the inverter and the wiring with extreme caution.
- > Ensure that the modules are disconnected at the inverter prior to separation.
- → Be sure to observe the time intervals specified by the inverter manufacturer after switching off the inverter.
- → Make sure that the plugs can not be connected unintentionally.
- → Before working on the contacts, check them for safety extra-low voltage.







4 ELECTRICAL CONNECTION4.2 ELECTRICAL INSTALLATION SAFETY

4 ELECTRICAL CONNECTION 4.3 CONNECTION OF MODULES








4 ELECTRICAL CONNECTION4.4 AFTER INSTALLATION

5 GROUNDING



Protective Grounding

The modules must be grounded in accordance with the local statutory regulations.

6 FAULTS AND DEFECTS



DANGER! Risk of fatal injury due to electric shock!

- Do not attempt to fix any problems yourself (e.g., glass cracks, damaged cables).
- Please contact an installer or Q CELLS Technical Customer Service Department.

7 DISPOSAL

- ➔ Do not disconnect modules by yourself.
- Please contact an installer or Q CELLS Technical Customer Service Department.
- Dispose of modules in accordance with the local disposal regulations.

8 MAINTENANCE AND CLEANING

Q CELLS solar modules are known for a long operating life and minimal maintenance effort and expense. Dirt and grime are usually washed away by rain. If the module is fully or partially shaded by dirt or debris (e.g., plants, bird droppings), it needs to be cleaned to prevent a loss of performance.

Maintenance

- The PV system has to be inspected regularly by certified personnel
- The time intervals and extent of the inspection can depend on local circumstances (e.g. salt, ammonia content in the air, high humidity etc.). The customer/operator must inform himself about time intervals and extend of necessary inspections.
- Inspections have to be performed especially after extraordinary events (e.g. storm, hail, high snow loads etc.)
- During the inspections it has to be checked that the components are secure, undamaged and clean

Cleaning



WARNING! Risk of injury due to hot and live modules!

- Only clean modules that have cooled down.
- ⇒ Do not carry or wear any electrically conductive parts.

WARNING!

Risk of falling due to unsecured access!

- Never access the installation area alone or without taking adequate security precautions.
- Please commission a trade specialist.




NOTE! Module surface damage may occur!

- Remove snow and ice carefully without force (e.g. with a very soft broom).
- Do not scratch off dirt.
- Rinse dirt (dust, leaves, etc.) off with lukewarm water or use an alcohol based glass cleaner. Do not use abrasive detergents or surfactants.
- Use a soft cellulose cloth (kitchen roll) or sponge to carefully wipe off stubborn dirt. Do not use micro fleece wool or cotton cloths.

Isopropyl alcohol (IPA) can be used selectively to remove stubborn dirt and stains within one hour after emergence.


- Please follow the safety guidelines provided by the IPA manufacturer.
- Do not let IPA run down between the module and the frame or into the module edges.

Note! Module damage may occur! Do not clean modules with water if there is a risk of frost.





Free the substructure from any dirt and debris (leaves, bird nests, etc.).



OT Thalheim Sonnenallee 17–21 06766 Bitterfeld-Wolfen Germany

 TEL
 +49(0)34946699-23222

 FAX
 +49(0)34946699-23000

 EMAIL
 sales@q-cells.com

 WEB
 www.q-cells.com

Subject to change without notice. © Q CELLS Installation manual solar modules Q.PEAK DUO-G9.X_2020-09_Rev01_EN